



LOSS OF SOME TREE SPECIMENS/VEGETATION TO FACILITATE EXTENDED VISIBILITY SPLAY

EXTENSION OF 30MPH SPEED LIMIT TO IMMEDIATELY SOUTH OF RUGBY CLUB ENTRANCE

2M WIDE FOOTWAY

PROPOSED RESIDENTIAL DEVELOPMENT

PROPOSED SITE ACCESS IN & OUT

3M WIDE FOOT/CYCLEWAY, SET BACK FROM MAIN ROAD

WIDE VERGE, TO RETAIN TREE SPECIMENS, WHERE POSSIBLE

TACTILE PAVING

PEDESTRIAN LINK TO EXISTING PROW

PRIMARY SCHOOL EXIT FOR BUSES & STAFF

WOODEN BOLLARDS SET 2M APART ALONG SCHOOL FRONTAGE TO DETER ON STREET STUDENT DROP OFF

3M WIDE FOOT/CYCLE WAY ACROSS FRONTAGE OF SCHOOL LAND, SET BACK FROM MAIN ROAD

LOSS OF SOME TREE SPECIMENS/VEGETATION TO FACILITATE VISIBILITY SPLAYS

PROPOSED PRIMARY SCHOOL LAND

PRIMARY SCHOOL ENTRANCE FOR BUSES & STAFF

PRIMARY SCHOOL PEDESTRIAN ACCESS

PROPOSED COLLEGE LAND

3M WIDE FOOT/CYCLEWAY

PROJECT IXWORTH ROAD, THURSTON	DATE 03.11.16	DRAWING STATUS INFORMATION	
DRAWING TITLE IXWORTH ROAD PROPOSED ACCESS STRATEGY	SCALE(S) 1:500	DESIGNED AF	DRAWN AF
CLIENT PERSIMMON HOMES	JOB No 1041	CHECKED MDA	APPROVED MDA
	DRAWING No 06/011	REVISION F	



REV	DATE	AMENDMENT DETAILS	DRAWN	APPROVED
F	25.05.17	INCREASE VISIBILITY SPLAYS TO THE NORTH TO 120m	MDA	MDA
E	11.05.17	UPDATE COLLEGE LAND AND PRIMARY SCHOOL LAND ANNOTATION	MDA	MDA
D	13.04.17	INCLUDE 90m VISIBILITY SPLAYS	MDA	MDA
C	16.11.16	REINSTATE SECTIONS OF FOOT/CYCLEWAY	AF	MDA
B	15.11.16	UPDATE FOOTWAY PROVISION	AF	MDA
A	15.11.16	SET BACK FOOT/CYCLEWAY TO AVOID TREE SPECIMENS	AF	MDA

NOTES:

- DRAWING BASED ON TOPOGRAPHICAL SURVEY CARRIED OUT BY BB SURVEYS DATED 25 MARCH 2016.

KEY:

- 2.4m x 120m VISIBILITY SPLAY TO NORTH (BASED ON 43.5mph DESIGN SPEED)
- 2.4m x 128m VISIBILITY SPLAY TO SOUTH (BASED ON 46.1mph DESIGN SPEED)
- - - 2.4m x 128m VISIBILITY SPLAY TO SOUTH (TO TANGENT)